KOLAR DIVISION.

Notice dated 4th November 1903.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 30th November 1903, for restoring Chillapally tank, Registered No. 370, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates tendered should include royalty on stones, etc., removed from the Government lands.

Description of work.	Unit of work.	Rate per unit.

4. Each tender must be accompanied by a deposit of Rs. 200 in Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Chillapally tank, Registered No. 370, Kolar Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor, will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	Per	Quantity.
Bund—		
Earthwork	C. yd.	22,308
Turfing	S. yd.	14,129
New stone work	C. yd.	4,336
Old do	„	1,769
Gravel backing	„	2,004
Removing and re-setting grade stones	Each	47
Do index stones	„	47
Gauge stones	„	1
Date stone	„	1
B. M. stones	„	2
Sluices—		
Examining and repairing	Each	3
Waste-weirs—		
Right weir 294′ long, repairing left weir 472′ long extending from 198′ to 472′.	Lump sum.	
Earthwork draft clearing	Do	
Dismantling left return and repairing the present body wall and return.	Do	
Burnt brick in surki mortar	C. ft.	6,176
Burnt stone slabs	S. ft.	1,045
Chunam plastering	Sq.	2416
Rough stone work, new	C. yd.	175

B. SUBBA RAO, *Executive Engineer.*